

**ANTEMASURATOARE**  
**LICEUL TEHNOLOGIC G. MOISIL**  
**Inlocuire ferestre corp liceu (demont., proc.,**  
**ref.spaleti si pervaze) - R.C. 2019**

NR CRT	COD ARTICOL DEVIZ	DENUMIRE CATEGORIE LUCRARI	U.M.	CANT.
	RPCT33A1	Demontare usi si ferestre din lemn	mp	131,80
	RPCJ13B1	Rep.tenc.spaleti	m	230,00
	RPCR24A	Zugraveli lavab.ptr.inter.pe tenc.exist.	mp	72,00
	RPCJ36A1	Glet ipsos pe tenc int.drisc.3 mm gr.exec.cu pasta ipsos la pereti si stalpi	mp	72,00
		Procurare,transport si montare ferestre profil PVC alb, minim 5 camere, geam termoizolant 3 straturi LOWE+ARGON+FLOAT+ARGON+FLOAT	mp	131,80
	CK09A1*	Procurare, transport si montare pervaz interior din PVC, la ferestre	m	63,40
	CK09A2*	Procurare, transport si montare pervaz exterior din Al, la ferestre	m	63,40
	TRB05B15	Transport mat.purtare directa peste 25kg.distanta 50m	to	5,00
	TRA01A10P	Transport auto moloz la 10 km	to	5,00

Intocmit,  
Baltoiu Titiana

